

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. 0-21

R.D.: N.F.J.D.

Co. Survey No:

T.49., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T48 R32E |

N1/16 |

S231624 |

1994 |

PLS 2405 |

None. Corner established this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |

Filed At |

Object ID |

PLANE CO-ORD |

State Zone |

X |

Y | DESCRIBE CORNER LOCATION:

Estab.By | Corner falls on west side of N-S ridgetop of P.Pine and scattered D. Fir. N-S draw bottom is 400' west.

Signature:

*Sue Newstetter*

Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 26" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Douglas Fir, 9" dia., bears N60°05'W, 15.0 ft., scribed: N 1/16 S23 BT  
Ponderosa Pine, 11" dia., bears N31°38'E, 7.8 ft., scribed: N 1/16 S24 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' south and west of  
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT  
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze  
and Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/17/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. 0-21

T.4S., R.32E., W.M.