

INDEX No. 0-23

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
C
N1/16 | S24
C
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 16" in the ground and raised a mound of stone around the monument.

From which:

- Ponderosa Pine, 10" dia., bears N28°22'W, 164.8 ft., scribed:C-N1/16 S24 BT
- Ponderosa Pine, 18" dia., bears N00°42'E, 119.1 ft., scribed:C-N1/16 S24 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' east of the monument and a steel fence post with Property Boundary (54-2) sign 21' west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

Susan E. Newstetter

OREGON
JULY 26, 1989
SUSAN E. NEWSTETTER
2405

Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 20, 1994

RECEIVED BY

Umatilla County Surveyor

Date 1-95

Rec'd By KK

No. 95-15-8

Office of _____ County of N-23
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)