

USDA FOREST SERVICE  
Index

CORNER RECORD (SEARCH)

File No. 0-23  
T.4S., R.32E.  
Meridian: Willamette

R.D.: N.F.J.D.  
N.F.: UMATILLA

Co. Survey No:  
County: Umatilla

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T48 R32E |  
C | None. Corner established this survey.  
N1/16 | S24 |  
C |  
1994 |

PLS 2405 | DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |  
Filed At |  
Object ID |

PLANE CO-ORD |


State Zone |

X |

Y | DESCRIBE CORNER LOCATION:

Estab.By | Corner falls on west slope of P.Pine and D.Fir. Old  
road is 2 ft. west.

Signature:



Title: Land Surveyor

Date: 10/20/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 16" in the ground and raised a mound of stone around the  
monument. From which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Ponderosa Pine, 10" dia., bears N28°22'W, 164.8 ft., scribed: C-N1/16 S24 BT  
Ponderosa Pine, 18" dia., bears N00°42'E, 119.1 ft., scribed: C-N1/16 S24 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' east of the monument  
and a steel fence post with Property Boundary (54-2) sign 21' west of the  
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe  
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and  
Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/20/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. 0-23

T.48., R.32E., W.M.