

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. O-24

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

T4S R32E

NE 1/16

None. Corner established this survey.

S24

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X

Y

Estab.By

DESCRIBE CORNER LOCATION:

Corner falls 50 ft. west of draw bottom which runs  
S40°E.

Signature:

*Sue Newstetter*

Title: Land Surveyor Date: 10/21/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 26" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Englemann Spruce, 12" dia., bears N05°02'E, 17.5 ft., scribed: NE 1/16 S24 BT  
Englemann Spruce, 18" dia., bears N80°27'E, 40.2 ft., scribed: NE 1/16 S25 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings based  
on the survey control network. Set steel fence post with Land Survey Monument  
(54-9) and Property Boundary (54-2) signs 5' south and west of the monument.  
Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken  
this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey  
Monument (54-9) signs on back of each tree as required. Painted a 6" red band  
above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/21/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. 0-24

T.4S., R.32E., W.M.