

Index
File No. P-11

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor.
No. _____

T 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

C 1/4

S 21

PLS 1106

1992



DESCRIBE CORNER MONUMENT FOUND

None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls in open, on Southwesterly slope, posted line E & W.

Signature

Will R. Wells

Title Division

Land Surveyor

Headquarters

Pendleton, Ore.

Date

6-11-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position established by survey...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap 10" in ground surrounded with mound of earth and stone set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

Compass declination 18° East.

9

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 11" ponderosa pine brs N60 1/4° E, 97.3' dist mkd C1/4S21 BT.

A 17" ponderosa pine brs N82 1/2° E, 103.1' dist mkd C1/4S21 BT.

A 22" ponderosa pine brs S61° W, 118.0' dist mkd C1/4S21 BT.

A 18" ponderosa pine brs S77° W, 111.9' dist mkd C1/4S21 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R. Wells Title Land Surveyor Date 6-11-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared? Yes XXX Filed At Umatilla County Surveyor Date 7-92

11

REMARKS

12

Index File No. p-11 T. 4 S. R. 32 E. M. Tract or Surv. No. WM. Cor. 13