

Index
File No. P-115
T 4 S R 32 E
Merid. Willamette

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or
Survey No. _____
Cor. No. _____

R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM
T 4 S R 32 E
C 1/4
S 21
PLS 1106
1992



DESCRIBE CORNER MONUMENT FOUND
None. Corner established as part of this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
None.

PHOTO IDENTIFICATION DATA
Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature _____

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER
Corner falls on Southerly slope about 7' South of E-W fence, posted line E & W.

PLANE COORDINATE POSITION DATA
State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency _____

Signature Willie R. Wells Title Land Surveyor Division _____ Headquarters Pendleton, Ore. Date 6-12-92 FS-7100-52 (3/68)

CORNER (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At position determined by survey...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap 12" in ground surrounded with mound of earth and stone set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.

Compass declination 18° East.

9

ACCESSORIES: DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 17" ponderosa pine brs N78 1/2° W, 62.6' dist mkd C1/4S22 BT.

A 11" ponderosa pine brs N21° W, 17.8' dist mkd C1/4S22 BT.

A 15" ponderosa pine brs N5° E, 39.6' dist mkd C1/4S22 BT.

A 12" ponderosa pine brs N51° E, 40.0' mkd C1/4S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By: W.R.Wells Title: Land Surveyor Date: 6-18-92 State Registration No. ORLS 1106 or Agency

Certified Cor. Record Prepared? Yes Filed At: Umatilla County Surveyor Date: 7-92

11

REMARKS

12

Index File No. P-15 T. 4 S R. 32 E

Tract or Surv. No.

Cor.

13