


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

P-17

History of original corner establishment:

Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 390, dated May 12, 1881. Surveyor General records state:
Set basalt stone 24 x 16 x 4 on South slope for 1/4 Sec. Cor.



Description of corner evidence found:

Found basalt stone 24 x 19 x 6" lying on it's side with no marks evident.

A 29" douglas fir snag brs N77 3/4°W, 32.9' with mostly healed blaze with no scribing visible.

A 37" douglas fir snag brs East, 38.4' with scribing visible.

Note: ' The above bearing trees appear to be original, but there is no original record for them.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the position of the found stone...

Set a 2 1/2" X 30" aluminum pipe with 2 1/2" aluminum cap 22" in ground surrounded with mound of earth and stone. Set steel fence post next to corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram. Set original stone alongside of new monument in mound.

New bearing trees established:

- A 11" ponderosa pine brs S67°E, 36.4' mkd 1/4S23 BT.
- A 7" ponderosa pine brs S76 1/2°E, 74.5' mkd 1/4S23 BT.
- A 12" ponderosa pine brs N7 1/4°W, 65.9' mkd 1/4S22 BT.
- A 12" ponderosa pine brs S73 1/2°W, 51.0' mkd 1/4S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly re-established to U.S.F.S. standards by me on June 09, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of.....County Surveyor..... County of.....Umatilla.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

P-17

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-92
Rec'd By KK
No. 92-80 B

☆ GPO-798-276