

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. P-19

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E

C1/4

None. Corner established this survey.

823

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X


Y

Estab. By

DESCRIBE CORNER LOCATION:

Corner falls on west slope of P.Pine and D.Fir. N-S draw bottom is 200' west. E-W fence is 40' north.

Signature:



Title: Land Surveyor

Date: 11/2/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 12" in the ground and raised a mound of stone and earth, 3
ft. dia. x 1 ft. high. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 14" dia., bears N65°02'W, 19.7 ft., scribed: C1/4 S23 BT
Ponderosa Pine, 12" dia., bears N79°53'E, 7.8 ft., scribed: C1/4 S23 BT
Ponderosa Pine, 8" dia., bears S27°08'E, 35.5 ft., scribed: C1/4 S23 BT
Ponderosa Pine, 8" dia., bears S68°15'W, 12.4 ft., scribed: C1/4 S23 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 11/2/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-19

T.4S., R.32E., W.M.