

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. P-22

R.D.: N.F.J.D.

Co. Survey No:

T.48., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM

DESCRIBE CORNER MONUMENT FOUND

T48 R32E

W1/16

None. Corner established this survey.

C-----C

S24

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X

Y

DESCRIBE CORNER LOCATION:

Estab. By

Corner falls on east slope of D.Fir and P.Pine. N-S draw bottom is 100' west. E-W fence is 1' south. N-S road 50' east

Signature:

*Aue Newstetter*

Title: Land Surveyor

Date: 10/20/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 24" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Douglas Fir, 12" dia., bears N31°05'W, 36.4 ft., scribed: C-W1/16 S24 BT  
Douglas Fir, 12" dia., bears S49°59'W, 37.4 ft., scribed: C-W1/16 S24 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and south of  
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT  
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze  
and Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/20/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-22

T.4S., R.32E., W.M.