


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

p-9

History of original corner establishment:

Corner originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 390, dated May 12, 1881. Surveyor General records state: Set basalt stone 14x12x6 on South slope for 1/4 Sec. Cor. A fir 8 in. di. brs S23°E, 53 lks. dist. A fir 16 in. di. brs S12°W, 69 lks. dist.

Corner remonumented by Craig L. Wanless, BLM Cadastral Surveyor under instructions dated July 18, 1977. His record states: The 1/4 sec. cor. of secs. 20 & 21 monumented with the original unmarked basalt stone 14x12x6 ins., firmly set 6 ins. high, from which the original bearing trees; A fir 30 ins. diam., bears S23°E, 53 lks. dist., with healed blaze. A fir 30 ins. diam., bears S12°W, 69 lks. dist., with scribe marks 4 S visible on open blaze. At the corner point... Set an iron post 28 ins. long 2 1/2 ins. diam., 6 ins. in ground, to solid rock and in a mound of stone, 4 ft. base, to top, with brass cap mkd. (as shown in corner diagram) from which a new bearing tree... A fir 19 ins. diam., bears S17 1/2°E, 117 lks. dist., mkd. 1/4 S21 BT. Deposit corner stone alongside iron post.



Description of corner evidence found:

Found 2 1/2" iron pipe with 3 1/4" brass cap (as shown in corner diagram)

- A 32" douglas fir brs S10°W, 45.8' dist with scribing visible.
- A 18" douglas fir brs S17 1/2°E, 78.0' dist with scribing visible.
- A 32" douglas fir brs S25 1/2°E, 35.9' dist with healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Set steel fence post next to corner with sign 54-9 & 54-2 attached.

New bearing tree established:

A 13" ponderosa pine brs N53°E, 56.8' dist. scribed 1/4 S21 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on June 02, 1992.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of... County Surveyor County of... Umatilla
State of... Oregon I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 7-92
Rec'd By [Signature]
No. 92-80-B

☆ GPO-788-276

P-9