

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. Q-22

R.D.: N.F.J.D.

Co. Survey No:

T.48., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T48 R32E |

SW1/16 |

None. Corner established this survey.

S24 |

1994 |

PLS 2405 |

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA |

Photo No. |

Filed At |

Object ID |

PLANE CO-ORD |

State Zone |

X |

Y |

DESCRIBE CORNER LOCATION:

Estab. By |

Corner falls on east slope of D. Fir, Larch and L.P. pine.

A N-S draw bottom is 60 ft. west.

Signature: *Aue Hewstetter*

Title: Land Surveyor Date: 10/21/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 26" in the ground.
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Lodgepole Pine, 10" dia., bears N52°56'W, 10.1 ft., scribed: SW 1/16 S24 BT
Douglas Fir, 10" dia., bears S67°14'W, 30.4 ft., scribed: SW 1/16 S24 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/21/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. Q-22

T.4S., R.32E., W.M.