

Index
File No. R-11

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor.
No. _____

T 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

1 S 21
4 S 28

1977

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature _____

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency _____

DESCRIBE CORNER MONUMENT FOUND

Found 2½" iron post with ¾" brass cap (marked as shown in corner diagram) in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

- A 13" ponderosa pine brs S61°E, 17.6' with visible scribing.
- A 20" ponderosa pine brs N82½°W, 70.5' with visible scribing.
- A 12" ponderosa pine brs N1°W, 15.9' with visible scribing.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on NW slope posted line E & W.

Signature

Willie R. Wells

Title

Land Surveyor

Division

Headquarters

Pendleton, Ore.

Date

6-02-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post next to corner with sign 54-9 & 54-2 attached.

Compass declination 18° East.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing tree established:

A 13" ponderosa pine brs S17° E, 10.2' scribed 1/4S28 BT.

New BT has a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Work Done By W.R. Wells Title Land Surveyor Date 6-02-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared? Yes Filed At Umatilla County Surveyor Date 7-92

REMARKS

Index File No. R-11 T. 4 S R. 32 E W.M. Tract or Surv. No. Cor. 13