

Index

File No. R-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

1 S 22

4 S 27

1992

PLS 1106



DESCRIBE CORNER MONUMENT FOUND

No trace of original post.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found rotted remains of a 22" douglas fir stump, brs N24°W, 14 lks(9.2'). Remains of blaze face & fragmentary scribes & axe marks were found at base of stump. The stump is very rotten.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner located on North slope about 300' North of edge of bare ridge.

Signature

Will R. Wells

Title
Land Surveyor

Division

Headquarters
Pendleton, Ore.

Date
6-04-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Re-established corner by reversing record call, measuring to where blaze face would have stood. Set a 2½"x30" aluminum pipe with 2½" aluminum cap 26" in ground surrounded with mound of earth and stone & 6' steel fence post East of corner and attached signs 54-2 & 54-9. Cap marked as shown in corner diagram.
Compass declination 18° East.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BT's established:

A 15" western larch brs N50½°W, 20.1' scribed 1/4S22 BT.

A 10" western larch brs N39½°E, 20.0' scribed 1/4S22 BT.

A 11" western larch brs S85½°W, 44.8' scribed 1/4S27 BT.

A 12" western larch brs S63°E, 25.9' scribed 1/4S27 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Work Done By W.R. Wells Title Land Surveyor Date 6-04-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes XXX Filed At Umatilla County Surveyor Date 7-92

REMARKS

Index File No. R-15 T. 4 S. R. 32 E. W.M. Tract or Surv. No.

Cor.

Index
File No. R-15

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____
Cor. No. _____


T 4S R. 32E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Material: None ~~Size: None~~
 Height Above Ground: ~~None~~ ~~Condition: None~~
 Markings: ~~None~~

2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

There is an old location poster on the hogback approx. 200' West of assumed 1/4 corner location. It states "3 chains East to 1/4 corner". There are old "Timber Sale Boundary" posters through to assumed 1/4 corner location but there is no evidence of cutting.

There are several old down and very rotten fir and (OVER)

3

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Approx. 1/4 corner location is about 500 ft. North of Primitive Road. Road is on open ridge top.

See Owens Butte 7.5 minute quad map for access.

4

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
 Signature _____ 7

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
 Agency _____ 8

Signature

T. Hollamon

Title
Eng, Tech.

Division

Headquarters

Date

4-8-77

7100-52-(3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

9

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

10

Work Done By _____ Title _____ Date _____ State Registration No. or Agency _____

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

3 continued

W. larch in the area but no evidence of corner or bearing trees could be found.

12

Index File No. T. R. M. Tract or Surv. No. Cor. 13