


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-16

History of original corner establishment:

None. Corner established as part of this survey.



Description of corner evidence found:

Found a Kinzua tag and old location poster located near corner point.

Description of monument and accessories established to perpetuate the original location of this corner:

At position established by survey... Set a 2 1/2"x30" aluminum pipe with 2 1/2" aluminum cap 8" below road surface. Set steel fence post 9.6' North of corner at edge of road with sign 54-2 and 54-9 attached.

New bearing trees established:

A 12" western larch brs S87 1/2° W, 44.5' scribed E1/16S27 BT.  
A 7" western larch brs N54 1/2° W, 57.8' scribed E1/16S22 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

Compass declination 18° East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards by me on June 09, 1992.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of County Surveyor County of Umatilla Oregon I hereby certify that the within instrument was filed in this office for record on the day of 1992

(COUNTY OFFICIAL) by (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY Umatilla County Surveyor Date 7-92 Rec'd By KR No. 92-80-B R-16