

INDEX No. T-18

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
W1/16
C-----C
S26
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

Ponderosa Pine, 12" dia., bears S05°56'E, 14.9 ft., scribed: C-W1/16 S26 BT

Ponderosa Pine, 12" dia., bears S82°30'W, 33.3 ft., scribed: C-W1/16 S26 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.



Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
November 2, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By RK
No. 95-15-B

Office of _____ County of _____ State of _____ I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ by _____
(COUNTY OFFICIAL) (DEPUTY)

T-18