

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. T-21

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM

T4S R32E

1/4

S26|S25

1994

PLS 2405

DESCRIBE CORNER MONUMENT FOUND

Found a 12"x10"x8" basalt stone maked 1/4, set firmly in the ground. Accepted as original position.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found an unrecorded bearing tree, a Ponderosa Pine, 48" dia., with scribing visible, which bears N07°42'E, 8.5 ft. from the original stone.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

X


Y

Estab.By

DESCRIBE CORNER LOCATION:

Corners falls on gentle west slope of P.Pine and D.Fir. Old N-S fence is 1 ft. east.

Signature:



Title: Land Surveyor Date: 10/26/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Moving the original corner stone aside I set in it's place a 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground and buried the original stone north alongside the monument. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 9" dia., bears N53°41'W, 47.4 ft., scribed: 1/4 S26 BT
Douglas Fir, 14" dia., bears N73°12'E, 50.0 ft., scribed: 1/4 S25 BT
Douglas Fir, 18" dia., bears S47°21'E, 39.9 ft., scribed: 1/4 S25 BT
Ponderosa Pine, 14" dia., bears S61°11'W, 47.3 ft., scribed: 1/4 S26 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and south of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/26/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. T-21

T.4S., R.32E., W.M.