

INDEX No. T-25

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

DIAGRAM
T4S
1/4
R32E R33E
S25|S30
1977

Set basalt stone 14x12x5 on S.E. slope for 1/4 Sec. Cor.

A Pine 5 in. dia. brs N80°E, 17 lks dist.
A Tamarack 18 in. dia. brs. S60°W, 3 lks. dist.

In 1977 the Bureau of Land Management (BLM) conducted a remonumentation of certain original corner points in T.4S., R.32E., W.M., under Special Instructions dated May 3, 1957, Group 350. Their record states:

The 1/4 sec. cor. of secs. 25 and 30, on the E. bdy. of the tp., monumented with the original basalt stone, 14x12x5, loosely set 1 in. in the ground, mkd. 1/4 on N. face, from which the remains of an original bearing tree: A larch stump, 22 ins. diam., bears S60°W, 3 lks. dist., with scribe marks 1/4 S BT visible on open blaze. At the corner point set an iron post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, and in a mound of stone, 3 ft. base, to top, with brass cap mkd. (SEE DIAGRAM) from which new bearing trees: A grand fir, 10 ins. diam., bears N 83°E, 21 lks. dist., mkd. 1/4 S30 Bt. A lodgepole pine, 5 ins. diam., bears S20°W, 44 1/2 lks. dist., mkd. X BT. Deposit corner stone alongside iron post.

Description of Corner Evidence Found:

Found iron monument, in a mound of stone, with a brass cap marked as shown in DIAGRAM. Monument is solid and firm.

Western Larch stump, 20" dia, with scribing 1/4 S BT visible, bears S60°38'W, 2.0 ft. (Org. Rec: S60°W, 1.98ft)

Douglas Fir, 14" dia., with healed blaze, bears N74°50'E, 13.0 ft. (BLM Rec: N83°E, 13.86 ft.)

Description of monument and accessories I established to perpetuate the original location of this corner:

No work is needed on the monument.

From Which:

Western Larch, 18" dia., bears S82°00'E, 40.8 ft., scribed: 1/4 S30 BT

Western Larch, 6" dia., bears S32°30'W, 14.8 ft., scribed: X BT

Lodgepole Pine, 8" dia., bears N83°15'W, 15.5 ft., scribed: 1/4 S25 BT

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 17, 1994

REGISTERED PROFESSIONAL LAND SURVEYOR
Susan E. Newstetter

OREGON
JULY 26/1989
SUSAN E. NEWSTETTER
2405

Renewal Date: 12/3/96

1-95
RK
95-15-B

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

T-25