

INDEX No. V-19

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

Set basalt stone 14x12x3 on west slope for 1/4 sec. cor.

A tamarack 14 in. dia. bears N8°W, 53 lks dist. A fir 12 in. dia. bears S23°E, 28 lks dist.

DIAGRAM

T4S R32E
S26
1/4
S35
1994
PLS 2405

Description of Corner Evidence Found:

Could not find original stone. I believe it was lost to road building or logging.

Found the remains of the original fir bearing tree. It is now a rotted stump, pushed over, with scribing 1/4 S BT visible. Tied root hole. Rec: S23°E, 28 lks (18.48 ft.)

The original tamarack bearing tree is gone.

Description of monument and accessories I established to perpetuate the original location of this corner:

From the reversed record of the original bearing tree (N23°W, 18.48 ft.) I set a 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 26" in the ground.

From Which:

- Ponderosa Pine, 9" dia., bears N63°08'W, 107.4 ft., scribed: 1/4 S26 BT
- Douglas Fir, 10" dia., bears N72°49'E, 69.9 ft., scribed: 1/4 S26 BT
- Ponderosa Pine, 12" dia., bears S30°22'E, 60.4 ft., scribed: 1/4 S35 BT
- Ponderosa Pine, 14" dia., bears S77°37'W, 99.2 ft., scribed: 1/4 S35 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

Susan E. Newstetter

OREGON JULY 26, 1989 SUSAN E. NEWSTETTER 2405

Renewal Date: 12/31/96

This work was performed by: Susan E. Newstetter PLS 2405 Witnessed by: Rick Saul and Rick Pewonka November 4, 1994

RECEIVED BY

Umatilla County Surveyors Date 1-95 Rec'd By KR No. 95-15-B

Office of _____ County of _____ State of _____ I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19 _____ by _____ (COUNTY OFFICIAL) (DEPUTY)