

INDEX No. V-22

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
S25
W1/16
S36
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 6" in the ground and raised a mound of stone, 4 ft. dia. x 2 ft. high around the monument.

From Which:

Ponderosa Pine, 10" dia., bears N31°40'W, 36.6 ft., scribed: W1/16 S25 BT

Ponderosa Pine, 14" dia., bears S47°01'E, 40.7 ft., scribed: W1/16 S36 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.



Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 26, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By KK
No. 95-15-B

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was ✓-22
filed in this office for record on the _____ day of _____, 19____
by _____
(COUNTY OFFICIAL) (DEPUTY)