

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. V-23

R.D.: N.F.J.D.

Co. Survey No:

T.48., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM	DESCRIBE CORNER MONUMENT FOUND
T4S R32E	Found iron monument, extending 6 inches from the ground.
S25	Monument is solid and in good shape.
1/4 _____	
S36	
1977	
(BLM Cap)	DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
PHOTO ID DATA	Ponderosa Pine, 20" dia., scribing visible, bears N55°52'W, 15.2 ft. (Org. Rec: N52°W, 15.18 ft.)
Photo No.	Tree is alive and well.
Filed At	
Object ID	Ponderosa Pine, 30" dia., scribing visible, bears S38°28'E, 19.6 ft. (Org. Rec: S44°E, 17.82 ft. BLM Rec: S37°E, 20.79 ft.) Tree is alive and well.
PLANE CO-ORD	
State Zone	
X	
Y	DESCRIBE CORNER LOCATION:
Estab.By	A N-S road is approx. 550 ft. west.

Signature: 

Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.

No work is needed on the monument.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE

Ponderosa Pine, 20" dia., bears N86°30'E, 39.1 ft., scribed: 1/4 S25 BT

5/8"x30" rebar, set approx. 28 ins. in the ground, with yellow plastic

cap marked PLS 2405 bears: S58°45'W, 7.9 ft.

Measurements to BT and rebar taken with a magnetic compass, declination 20°

East, and a nylon clad steel tape. Set steel fence post with Land Survey

Monument (54-9) and Property Boundary sign (54-2) signs 5' north and east

of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT

scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze

and Land Survey Monument (54-9) signs on back of each tree as required.

Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/17/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. V-23

T.4S., R.32E., W.M.