


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

x-25

History of original corner establishment:

The corner was originally established by George S. Pershin under Contract No. 390 dated May 12, 1981. The original notes state that a basalt stone 16" x 8" x 5" was set on West bank of creek from which: a tamarack 8" dia. bears S 12° E 17 lks (11.22 ft) A fir 8" dia. bears N 22° W 12 lks (7.92 ft)



No record of subsequent remonumentation found in County Records .

Description of corner evidence found:

None - corner re-established by survey.

Description of monument and accessories established to perpetuate the original location of this corner

At the corner position a 2 inch by 30 inch iron pipe, with brass cap marked as shown, was set 26 inches in the ground and surrounded with a mound of stones to the cap .

Set steel fence post South of corner and attached signs 54-4 & 54-2.

Established 2 new BT's: A 18" Tamarack bears N 25° W 76.3 ft scribed 1/4 S 36 BT.

A 15" Red Fir bears N 1° W 43.2 ft scribed 1/4 S 31 BT.

New BT's have a lower Blaze scribed BT with a brass washer stamped PLS 1106 nailed to it.

BT's have 54-3 & 54-4 signs attached & a 6" red band painted around them above Blaze.

Used steel tape and magnetic compass with 19 1/2° east declination . Measured to center of Bts.
See map of survey


This corner set July 26, 1979

Witnesses: Greg Flowers, L.S.I.T.
Brent Reynolds

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106



Office of County Surveyor County of Umatilla
Oregon, I hereby certify that the within Instrument was filed in this office
for record on the day of

..... by
(COUNTY OFFICIAL) (DEPUTY)

x-25
RECORDED BY
Date August 20, 1979
Rec'd by M. Hughes
No. Q-1134-B. corresponding drawing