


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-21

History of original corner establishment:

In 1881, under Glo Contract No. 410, George S. Pershin set a stone 18x12x6, from which a 9" Pine bears N67°W, 60 lks.; an 8" Pine bears N70°E, 21 lks.; an 8" Pine bears S36°E, 39 lks.; and a 7" Pine bears S47°W, 30 lks.



Description of corner evidence found:

Found stone 16"x9"x7" firmly set with 5 notches on SE corner, 1 notch on NW corner.

No bearing trees found. Root hole with dead & down & rotted tree S36°E, 25.7 ft., no scribing.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x31" aluminum pipe with 3 1/4" aluminum cap rising 4", stamped:

New BT's:

- A 5.0" L. Pine bears N35°W, 17.0 ft., scribed T3S R33E S35 BT.
- A 5.1" L. Pine bears N60°E, 28.8 ft., scribed T3S R33E S36 BT.
- A 5.2" L. Pine bears S40°W, 9.7 ft., scribed T4S, R33E S2 BT.
- A 6.0" L. Pine bears S55°E, 13.1 ft., scribed T4S R33E S1 BT.

	T3S
R	
33	S35 S36
E	S2 S1
	1983
	LS 1848
	T4S

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982. Set metal fence post 4 ft. north of corner.

Compass Declination: 19 1/2°E Witness: N. Petz

From 2110 northeasterly 1.5 mi. to posted south line, S 36, Corner is west 220 ft. downhill in lodgepole thicket.

I hereby certify the above described corner monument and/or accessories was established as described on September 13, 1983.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

B. A. Sutton
OREGON
JULY 13, 1979
B. A. SUTTON
1848

Office of Surveyor County of Wasco
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 13th day of July 1983
David Kumbier by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)

2-21