


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-17

History of original corner establishment:

In 1881, under Glo Contract No. 410, George S. Pershin set a stone 18x12x5, from which a 4" Pine bears N85°W, 30 lks.; a 17" Pine bears N41°E, 49 lks.; a 10" Fir bears S6°E, 47 lks.; and an 18" Fir bears S13°W, 59 lks.



Description of corner evidence found:


Found original stone with 5 notches.

Bearing Trees Found:

- A 27" P. Pine bears N44 1/4°E, 32.4 ft., B&S visible "R33EBT".
- A 20" leaning Fir bears S5°E, 31.5 ft., B&S visible "T4S R33E S11".
- A 31" D. Fir bears S18°W, 38.9 ft., blaze visible. Did not open.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum capped aluminum pipe, stamped: rising 14" in mound of stones, with original stone set north in hole.



New BT's:

- A 19 1/2" W. Larch bears N41 1/2°W, 100.6 ft., scribed T4S R33E S3 BT
- A 12" D. Fir bears S45°E, 63.7 ft., scribed T4S R33E S11 BT

Painted Blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982. Set metal fence post 4 ft. north of corner.

Compass Declination: 19 1/2°E

Witness: D. Scott

From the intersection of 5435 & 2110-054, go S45°E, 300 ft. to corner.

I hereby certify the above described corner monument and/or accessories was established as described on May 11, 1984.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 10<sup>th</sup> day of July, 1984  
David Krumbein by Betty Cochran  
 (COUNTY OFFICIAL) (DEPUTY)

84-86-17