


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by Frank W. Campbell in 1883 under contract No. 468
 Set was a basalt stone 20" x 12" x 5" in ground marked "1/4" on North side
 From which a 20" Fir bears N 52°W, 491ks and a 16" Pine bears S 56° E, 15 lks



N-11

Description of corner evidence found:

Found a stone of approximately the right size set in the ground with faint scribing on North side from which N 46° E, 20.00 feet is a 16" stump lying on the hill scribed "1/4 S".
 This stump had rolled down from higher on the hill
 A stump hole bears N 49 1/2° W, 9.0 feet
 A 12" Pine with scribing "1/4 S" "BT" laying on hillside with roots still firm in ground
 Since the stone was set in the ground I presumed that Campbell had reversed his distance and used the position of the stone

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" Brass Cap on a 2 1/2" galvanized pipe 6" in the ground with a 5 foot dia. stone mound to within 6" of the top stamped as shown:


From which I scribed the bearing trees
 A 14" Fir bears N 40° W, 30.7 feet scribed 1/4 S 16 BT.
 A 24" Ponderosa Pine bears S 74 1/2° W, 23.15 feet scribed 1/4 S 21 BT

August 6, 1984
 Witness: B. Reynolds
 S. Carlson

Bearing trees have: A Brass Washer stamped PLS 933 nailed to the BT scribe, a painted band around the tree and on the face of the scribe, signs # 54-3 & 54-4

Bearing trees were measured horizontally with a steel tape to the center of the tree and a magnetic compass with a 19° East variation.

Also set a steel fence post with sign # 54-4 by Brass Cap.



**REGISTERED
 PROFESSIONAL
 LAND SURVEYOR**

David H. Krumben

**OREGON
 JULY 17, 1970
 DAVID H. KRUMBEN
 933**

Office of Surveyor County of Wasatch
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 20 day of November, 1984
 by Billy Cochran
 (COUNTY OFFICIAL) (DEPUTY)

M-11