


History of original corner establishment:

George S. Pershin under G.L.O. contract number 410, dated July 28, 1881, set a basalt stone 20"X 10"X 4" fifteen inches in the ground from which:

- A Tamarack, 8" dia., N24°E, 40 lks.
- A Pine, 12" dia., S70°E, 15 lks.
- A Fir, 10" dia., S16°W, 62 lks.
- A Pine, 16" dia., N70°W, 60 lks.



Craig L. Wanless, Cadastral Surveyor, under special instructions Group Number 350 found the original stone from which:

- A root hole, N24°E, 40 lks., with down, decayed and scribed larch alongside

(Continued on Page 2 of 2.)

Description of corner evidence found:

I found a 2½" iron pipe with a 3" brass cap marked: in a stone mound. From the corner:

T4S R33E
S17 | S16
S20 | S21
1977

- A Ponderosa Pine snag, 17" dia., S70°E, 11.5 ft., with scribing visible.
- A Douglas Fir, 7" dia., N17°E, 20.0 ft., with a healed blaze.
- A Douglas Fir, 9" dia., S18°W, 30.0 ft., with a healed blaze.
- A White Fir, 9" dia., N59°W, 18.5 ft., with a healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

I marked a new BT:

A Tamarack, 12" dia., S12½°E, 92.4 ft., marked: T4S R33E S21 BT

BTs have blaze and a 6" band painted red, BT tags and "Attention" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 16°E.

April 21, 1987



Office of County Surveyor County of Umatilla
 State of Ore. I hereby certify that the within instrument was filed in this office
 for record on the 11th day of May, 1987
 Done at Umatilla by Fayette S. Munro
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 5-11-87
 Rec'd By [Signature]
 No. 87-25-R

GPO-798-276


N-9

History of original corner establishment:
(Continued from Page 1 of 2.)

- A Ponderosa Pine, 17" dia., S70°E, 15 lks. with scribing visible.
- A root hole, N50°W, 60 lks., with a down, decayed and scribed pine alongside.

He set an iron post 28" long, 2 1/2" dia., in a stone mound and marked new BTs:

- A Grand Fir, 7" dia., N27°E, 21 lks.
- A Grand Fir, 8" dia., S18°W, 45 1/2 lks.
- A Grand Fir, 8" dia., N59°W, 27 lks.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of *Wasco Co. Surveyor* County of *Wasco*
State of *OR* I hereby certify that the within instrument was filed in this office
for record on the *10th* day of *May*, 19 *87*
Dave Lemmon by *Fayette S. Munro*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

GPO-788-176

87-25-M

N-9
95.2