


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveyor General Records state:
 Seat basalt stone 13 X 8 X 7 ins. for cor. to secs 25, 26, 35 36 from which:
 A Pine 5 ins. dia. bears S 35° W, 15 lks. dist.
 A Pine 4 ins. dia. bears S 47° E, 10 lks. dist.
 A Pine 4 ins. dia. bears N 54° E, 20 lks. dist.
 A Pine 4 ins. dia. bears N 72° W, 10 lks. dist.




No record of subsequent remonumentation was found in county records.
 Description of corner evidence found:

Found marked stone in mound of stone.
 No trace of original BTs were found.

(See map of Survey, dated December, 1975)

Description of monument and accessories I established to perpetuate the original location of this corner

At corner position I set 2 1/2" X 30" iron pipe with brass cap marked as shown 24" in ground, from which:
 A 12" Tamarack bears N 25° E, 63.4 ft. marked T4S R331/2E S25 BT.
 A 12" Tamarack bears S 83° E, 28.0 ft. marked T4S R331/2E S36 BT.
 A 5" Lodgepole Pine bears S 11° W, 22.8 ft. marked T4S R331/2E S35 BT.
 A 15" Pine bears N 89° W, 62.6 ft. marked T4S R331/2E S26 BT.
 Buried stone East and along side pipe.
 Raised mound of stone.
 Set steel fence post 5+ ft. South.



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Duane J. Griffith
 OREGON
 JULY 10, 1936
 DUANE J. GRIFFITH
 644

Brass Washer nailed to BT blazes.
 Used steel tape and magnetic compass with 19° 30' East declination.
 Measured to center of all BTs.

Office of..... County of.....
 State of....., I hereby certify that the within Instrument was filed in this office for record on the..... day of.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

V-21