


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveror General Records state: Set a basalt stone 13 X 10 X 7 in. for cor. to Secs 25, 30, 31, 36 from which:
A Pine 10 in. dia. bears S 36° W, 20 lks. dist.
A Pine 8 in. dia. bears N 74° W, 10 lks. dist.
A Pine 10 in. dia. bears N 66° E, 60 lks. dist.
A Pine 15 in. dia. bears S 28° E, 48 lks. dist.



No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

Found NE and SW BTs and a mound of stone. Did not find marked stone, from which:
A 9" Pine bears S 33° W, 13.2 ft. scribes visible.
A 14" Pine snag bears N 66° E, 39.6 ft. scribes visible.

(See map of Survey, dated December, 1975)


Description of monument and accessories established to perpetuate the original location of this corner

At record distances from the NE and SW BTs I set 2 1/2" X 30" iron pipe with brass cap marked as shown 22" in ground, from which:

New BTs:

- A 20" Pine bears N 47° E, 54.8 ft. marked T4S R34E S30 BT.
- A 9" Pine bears S 46° E, 50.4 ft. marked T4S R34E S31 BT.
- A 18" Pine bears N 65° W, 29.4 ft. marked T4S R331/2E S25 BT.

Raised mound of stone 3 ft. base to top of cap.
Set steel fence posts 5+ ft. West and South.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1894
DUANE J. GRIFFITH
644

Brass Washer nailed to BT blazes.
Used steel tape and magnetic compass
with 19° 30' East declination.
Measured to center of all BTs.

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the day of.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

V-25