

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: J-11, North 1/4 corner of Section 16, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and drove charred stake, as per instructions. Re-established by J. C. Arnold, Umatilla County Survey No. 33, dated July 14, 1888. Notes state: deposit, in mound of smooth boulders, about 1 quart of charcoal and 3 RR tie spikes. Cadastral Retracement Record from the U.S. Engineers Department, dated 10/3/60. Retracement notes state: Located S87°55'50"W a distance of 13.6 feet from station 96+85.5 on the PWR line that was on WO-799-82. Also located S87°57'01"W, a distance of 2636.01 feet from Section Corner 9-10-16-15. A concrete monument tied by BPA, 1952. Maintained by G. Dennis Edwards, #951, Umatilla County Survey #91-01-B, found 3 5/8" diameter brass disc., (marked as shown in monument detail), 0.4 feet below the surface of ground. (believes it is Price 1943). New Accessories: Alum. Tag #951 in power pole bears N12°15' W 64.84 feet. Center of sanitary sewer manhole lid bears N62°06'E 58.70 feet. Also a steel fence post set on same bearing, 61.70 feet. Tag #951 in power pole Bears S07°23'E 105.86 feet. Steel fence post bears N 83°35'W 3.00 feet. Attached Bearing Object, Witness Cor. signs to steel fence posts and power poles.

MONUMENT AND ACCESSORIES FOUND:

Found a 3 1/2" brass cap in concrete marked as shown in "monument marking detail".

An aluminum tag stamped #951 in face of power pole (UECA) #095000 bears N 12°15' W, 64.84 feet.

Center of sewer manhole bears N 62°06' E, 58.7 feet.

An aluminum tag stamped #951 in face of power pole (UECA) #165903 bears S 07°23' E, 105.86 feet.

MONUMENT MARKING DETAIL:

U.S. ENGINEER DEPARTMENT
PORTLAND DISTRICT
T5N R28E
9

16
1/4 COR
Boundary Monument

MONUMENT SET:

New Accessories:

A perimeter fence corner (around pump house) bears N47°W, 167.45 feet.

Corner has steel fence post with witness post sign attached, N 83°35' W, 3.0 feet.

All accessories have bearing object signs attached.

All existing accessories have witness post signs attached.

LOCATION AND COMMENTS: From overpass of I-82 and Third Street take gravel road to right by power generating plant.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 824719.98

East: 8502942.72

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

98-101-C