

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: May 1998

CORNER DESIGNATION: J-19, North Quarter Corner Section 14, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under contract No. 101, dated August 5, 1861. Notes state: Set post in mound and drove charred stake, as per instructions. Corner position was calculated by D. Edwards, OPLS #951, Umatilla County Survey Record 88-45-C, Area 1-87, dated 1988. Edwards set a witness corner, 1/2" x 24" rebar, S 89°44'40" W, 306.47 feet along Section line, and a brass cap on iron pipe witness corner S 89°44'40" W, 250.00 feet from corner point.

MONUMENT AND ACCESSORIES FOUND:

A 5/8" iron rod witness corner bears S 89° 43' W, 306.4 feet.

A disturbed and bent brass cap on iron pipe witness corner bears S 89°44' W, 250 feet +/-.

MONUMENT MARKING DETAIL:

T5N R28E

1 S11

4 S14

1998

PLS 1106

MONUMENT SET:

At position determined by single proportional measure between the Northwest and Northeast corners of Section 14, set 2 3/8" brass cap on 1" x 30" galvanized iron pipe, marked as shown in monument marking detail, 12" below ground in log yard.

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 12" below ground, bears N 45° E, 36.1 feet.

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 34° E, 76.0 feet. Top of cap buried 12" below ground.

A brass washer stamped "PLS 1106", 1.0 feet above ground in South face of pole #113000 bears N 56° W, 337.3 feet.

All accessories have bearing object signs attached.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Ben Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 824937.15

East: 8513560.83

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

98-101-C