

OREGON CORNER RESTORATION FORM

SECTION: 18 TOWNSHIP: 5N RANGE: 29E J-1

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NW 18

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract #101 in 1861. He set post and made mound. In 1959 USA Corps Engineers set 3" BC in concrete.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 3" BC in concrete 4" above surface stamped as below.

MONUMENT DETAIL

T5N
 R28E R29E
 12|7
 13|18

OREGON STATE PLANE COORDINATES NORTH ZONE, NAD 83(91), Int Feet:

824894.52
 8521513.41

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 56° 15' 23" E 134.84'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 29° 37' 03" W 414.50'
- A 5/8" x 30" Iron Rebar with plastic cap # 951 bears N 79° 38' 49" W 260.98'
- A 5/8" x 30" Iron Rebar with plastic cap # 951 bears S 56° 12' 30" W 360.97'

LOCATION AND COMMENTS

From NW corner of Wanaket Wildlife Area on McNary Beach Road, go East along the Northerly Boundary 1.0 mile and North .25 mile to corner.

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH

SURVEYOR'S SEAL

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/05