

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: L-13, East quarter corner of Section 16, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and deposited charred stake, as per instructions. Re-established by Verl R. Fraley, Umatilla County Survey Record #Q-761-A, dated 1948. Field notes state: I set a 3/4 inch iron pipe for the West 1/4 corner of Section 15. Re-established by G. Dennis Edwards, Umatilla County Survey #88-45-C, dated August 8, 1988. Survey record states: Found 1/2" x 12" iron pipe 0.2 feet North and 0.3 East, Fraley 1949 for Van Slatte. Found 1/2" iron pipe Orig. use by some as 1/4 corner bears S 03°24'33" W a distance of 47.36 feet. Set a 1" x 16" iron pipe with brass cap. New Accessories: A metal fence post S 89°41' E, 14.1 feet. A metal fence post N 89°41' W, 21.6 feet.

MONUMENT AND ACCESSORIES FOUND: A 2 3/8" brass cap on a 1" iron pipe, 6" under gravel road, marked as shown in "Monument Marking Detail".

A 2" aluminum cap witness corner bears N 90° E, 13.95 feet.

An aluminum tag stamped #951 in face of UECA pole #150400 bears S 07°43' E, 108.60 feet.

A 2" aluminum cap witness corner bears N 54°24' W, 26.81 feet.

Aluminum caps are set on 5/8" iron pins, and are stamped with date, corner identification, distance to corner and LS #951.

MONUMENT MARKING DETAIL:

T5N R28E

1/4

16 | 15

1995

LS 951

MONUMENT SET:

New Accessories:

A brass washer stamped "PLS 1106" in North face of railroad tie, 1.5 feet above ground bears S 35° W, 45.60 feet.

Bearing object tags are attached to all accessories.

Steel fence posts with witness signs attached near each witness corner.

LOCATION AND COMMENTS: North on Lind Road by Umatilla watertank.

Note: The cap is marked 1995, not 1988. Find no record for the existing aluminum cap and aluminum tag accessories.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Ben Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 822142.52

East: 8505613.04

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-101-C Renewal 6-30-98