

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: L-5, East 1/4 Corner Section 18, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set a 1/4 Sec. post; made mound and drove charred stake, as per instructions. Re-established by John Kimbrell, Umatilla County Record #251, page 49, dated 1907. Record states: Set iron bolt and bar for 1/4 Sec cor. Re-monumented by G. Dennis Edwards, Umatilla County Survey Record #91-01-B, dated January 1991. Record states: Found a splintered 3/4" ID galvanized pipe approximately 30" long with a metal (steel) plug driven into the top with a punch mark at the center. Pipe was bent. Also found a steel post with a USACE witness sign attached. N 71°50' E 1.74 ft from galv. pipe. At location of the found 3/4" iron pipe, set a 2 3/8" brass cap attached to the top of a 1"x30" galv. pipe marked as shown in "Monument Marking Detail", and 0.4 ft. above the surface of ground. Placed found 3/4" pipe alongside and raised a mound of soil around cap. New Accessories: A light pole N 30°47'27" W 125.57 ft. w/Alum. Tag #951, Bearing Object & Witness Cor. signs attached. A 9" Locust tree N 74°19'13" E 79.51 ft. w/ Bearing Object sign & alum. Tag #951 attached. Dist to Alum. Tag. A Park Guard post S 57°27'17" E 44.83 ft. Bearing Object & Witness Cor. signs w/Alum. Tag #951 attached. A steel post S 81°52' W 2.10 ft. w/Bearing Object, Witness Corner signs attached. (All distances to Alum. Tags)

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/8" brass cap on 1" iron pipe, 5" above ground, marked as shown in "Monument Marking Detail".

Accessories Found:

Found aluminum tag stamped #951, in park guard post, bears S 57°27'17" E, 44.83 feet.

A steel fence post bears S 81° 52' W, 2.10 feet.

An aluminum tag stamped #951 in a PP&L light pole #189573 bears N 30°47'27" W, 125.57 feet.

MONUMENT MARKING DETAIL:

T5N R28E

1/4 18|17

1990

LS 951

MONUMENT SET:

New Accessories:

A brass washer stamped "PLS 1106", 2.3 feet above ground in a 12" Locust tree bears N 76° E, 79.33 feet.

A 3" diameter steel pipe 1.6 feet above ground bears S 77° W, 95.17 feet.

All accessories have bearing object tags attached.

Steel fence post near corner with witness sign attached.

LOCATION AND COMMENTS: On 7th Street between "B" and "C" streets, City of Umatilla, go South-Southwest, approximately 130 feet to corner.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:
North: 821901.70
East: 8495051.54

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-101-C

Renews 6-30-98