

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-1, the Northwest Corner of Section 19, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 18, 19, 13 & 24; made mound and drove charred stake, as per instructions. Re-established by Donald Staebler, Umatilla County Survey Record H-106-B, dated 1972. Record states: Set and marked brass disc, marked as shown in "Monument Marking Detail". Maintained by Frank A. Tuers, Dependent Resurvey, under Special Instructions dated April 11, 1975. Record states: Found corner monumented with an iron post, 2 1/2 ins. diam., firmly set, protruding 12 ins. above ground, and in a mound of stone, 2 1/2 ft. base, 6 ins. high, with brass cap marked as shown in "Monument Marking Detail". Add the marks BLM 1975 to brass cap. Corner re-established by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: Found a 2 1/2" brass cap on an iron pipe. This cap was set in 1972 by Don Staebler. It lies N 89°53'41" W 12.48 feet from my single proportion location for this corner. The date stamped on cap was 1971. The BLM added 1975 to this cap. Set by single proportion a 1" x 30" iron pipe with a brass cap, stamped T5N, S13 | S18

S24 | S19, 1990, LS 951, 0.4 feet above surface of ground and raised a soil mound around the brass cap. See my 1989 area one county survey. A steel guard post with bearing object and witness sign attached referencing B.M. Elev. 496.821 N 05°22'20" W 385.28 feet. A R/R tie with an Alum. tag #951 & Bearing. Object sign attached S 89°51'10" E 62.17 feet. Dist. to Alum. Tag. A steel fence post w/ Bearing Object, Witness sign attached South 1 foot. A steel Guard post w/Bearing Object & Witness sign attached referencing 1972 Brass Cap set by Staebler N 89°53'41" W 12.48 feet. Dist to Brass Cap.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/4" brass cap on 2 1/2" iron post, protruding 10" above ground, marked as shown in "Monument Marking Detail". Brass cap monument by Edwards, set on Survey No. 91-01-B, bears S89°51'16"E, 12.49 feet.

MONUMENT MARKING DETAIL:

T5N
R27E R28E
S13 | S18
S24 | S19
BLM 1975
1972

Oregon State Plane Coordinates, North
Zone, NAD 83(91), Int. Feet:
North: 819193.92
East: 8489779.77

MONUMENT SET:

Notes: Corner monument per Survey No. H-106-B was maintained.

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground, bears N 42° E, 113.44 feet.

A brass washer stamped "PLS 1106" 2.0 feet above ground in a fence post bears S 23° E, 189.12 feet.

The Northwest fence corner post of a perimeter fence around a power generator bears S 46° W, 282.80 feet.

A 5/8" x 36" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" 2" above ground, bears N 35° W, 126.64 feet.

All accessories have bearing object tags attached.

Corner has a steel fence post nearby with witness sign attached.

Both iron rods have steel fence posts nearby with witness signs attached.

LOCATION AND COMMENTS: From Northwest corner of new Umatilla City

Cemetery, go West on dirt road approximately 4400 feet to corner.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

98-101-C

REGISTERED
PROFESSIONAL
LAND SURVEYOR

WILLIAM R. WELLS
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Rmews 6-30-98