

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-13, Northeast corner of Section 21, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 15, 16, 21 & 22; made mound and drove charred stake, as per instructions. Re-monumented by G. Dennis Edwards, Umatilla County Survey Records #L-59-B. Set 1/2" iron rod over found stone. Re-monumented by G. Dennis Edwards, Umatilla County Survey Records #88-45-C. Set brass cap in conc. over a 1/2" rebar that I set over a stone in Survey #L-59-B.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap 4" below gravel road surface. Stamped as shown in "Monument Marking Detail".

Existing Accessories:

An aluminum tag stamped #951 in face of UECA pole #150004 bears N 04°03'30" E, 262.89 feet.

An aluminum tag stamped #951 in face of UECA pole #220900 bears N 82°57'40" E, 18.41 feet.

An aluminum tag stamped #951 in face of UECA pole #220901 bears S 03°34'40" E, 336.70 feet.

A 2" aluminum cap on 5/8" iron pin, witness corner bears N 90° W, 20.00 feet.

Aluminum cap is stamped with date, corner identification, distance to corner and LS #951.

MONUMENT MARKING DETAIL:

T5N R28E

S16 | S15

S21 | S22

1995

LS 951

MONUMENT SET:

All accessories have bearing object signs attached. Witness corner has steel fence post with witness post sign attached 6" beyond. UECA pole #220900 has witness post attached.

LOCATION AND COMMENTS:

North on Lind Road 1 mile form Blue Mountain Asphalt.

Note: No record found for accessories from 1995. We note cap is stamped 1995, not 1988.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke


Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 819470.78

East: 8505648.20



Will. R. Wells



Renews 6-30-98

98-101-C