

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-3, North Quarter Corner of Section 19, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and drove charred stake, as per instructions. Dependent Resurvey by Frank A. Tuers, under Special Instructions, Group Number 864, dated April 11, 1975. Record states: Point for the 1/4 sec. cor. of secs. 18 and 19, at proportionate distance; there is no remaining evidence of the original corner. Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap marked as shown in "Monument Marking Detail". Maintained by G. Dennis Edwards, Umatilla County Survey Record 91-01-B, dated January 1991. Record states: Found a 3 1/4" U.S. Dept. of Interior Brass Cap, stamped as shown (in monument marking detail), 0.3 ft. above surface of ground on a 2 1/2" OD Galv. steel pipe. New Accessories:

- Steel fence post w/Bearing Object sign N 50° W 0.24 feet.
- " " " w/ " " sign N 00°05'30" W 2.53 feet.
- Steel fence post w/ " " sign N 88°08'30" E 13.32 feet.
- Steel fence post w/ " " sign N 88°27'10" W 17.21 feet.

MONUMENT AND ACCESSORIES FOUND: A 3 1/4" brass cap 2" under the ground stamped as shown in "Monument Marking Detail".

Existing Accessories:

- A steel fence post bears N 88°08' E, 13.32 feet.
- A steel fence post bears N 88°27' W, 17.21 feet.
- A steel fence post bears N 00°00' W, 2.53 feet.

MONUMENT MARKING DETAIL:

U.S. DEPARTMENT OF THE INTERIOR

T5N R28E

1 S18

4 S19

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGMENT

MONUMENT SET:

New Accessories:

- A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", buried 12" below ground level bears S 47° E, 59.78 feet.
- A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", buried 12" below ground level bears S 25° W, 57.67 feet.
- All accessories have new bearing object tags attached.
- Witness sign attached to steel fence post that bears North, 2.53 feet.

LOCATION AND COMMENTS: 1/2 mile West of grave yard on dirt road.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 819228.06

East: 8492428.60

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

98-101-C

Renews 6-30-98