

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-5, Northeast Corner Section 19, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 17, 18, 19 & 20; made mound and deposited charred stake, as per instruction. Cadastral Retracement Record, U.S. Corps of Engineers, dated Sept. 2, 1959, states: 6" x 6" concrete post, set 1.0' below surface with a nail set in top of block and nail projects 0.01 above top of post with a 2" x 2" white witness post 2' West. Dependent Resurvey by Frank A. Tuers, under Special Instructions dated April 11, 1975, under Group No. 864. Notes state: The cor. of secs. 17, 18, 19 and 20, monumented with a concrete post, 6 x 6 ins. firmly set, 6 ins. below ground, with nail in center. This position is harmoniously related with other cors. in the area, has long been recognized as the cor. by adjacent landowners and private surveyors, and is accepted as the best available evidence of the original cor. position. At corner point: Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap (marked as shown in Monument Marking Detail). Deposit concrete post and set a steel fence post, 5 1/2 ft. long, 2 ft. in the ground, alongside the iron post. Corner maintained by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: Found a 3 1/4" Dept. of Interior (BLM) Brass Cap stamped, as shown in (Monument Marking Detail). This monument replace a conc. cylinder found at this location by Tuers. This cap is now in concrete at the surface of an asphalt street. New Accessories: Center of H2O manhole, N 41°18'30" W 54.24 feet, Power pole w/Alum. Tag #951, Bearing Object & Witness signs attached. N 46°07'20" E 44.97 feet, Dist to Alum. Tag. Power pole w/Alum. Tag #951, Bearing Object sign N 85°34'10" E 29.77 feet. Dist to Alum. Tag. Power pole w/Alum. Tag #951, Bearing Object & Witness Corner signs S 36°50'40" W 45.20 feet. Dist to Alum. Tag.

MONUMENT AND ACCESSORIES FOUND: Found 3 1/4" brass cap set flush with asphalt stamped (as shown in Monument Marking Detail).

Existing Accessories:

An aluminum tag stamped #951 in face of PP&L guy pole #170002 bears N 46°07'20" E, 44.97 feet.

An aluminum tag stamped #951 in face of PP&L power pole #170003 bears N 85°34'10" E, 29.77 feet.

An aluminum tag stamped #951 in face of PP&L light pole #199970 bears S 36°50'40" W, 45.20 feet.

MONUMENT MARKING DETAIL:

U.S. DEPARTMENT OF THE INTERIOR

T5N R28E

S18 | S17

S19 | S20

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGMENT

Oregon State Plane Coordinates,

North Zone, NAD 83(91),

Int. Feet:

North: 819262.86

East: 8495084.99

MONUMENT SET:

New Accessories:

The center of a water manhole marked with an "X" bears N 41° W, 54.22 feet.

LOCATION AND COMMENTS: Intersection of Madison and Cemetary Road in center of intersection.

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells

Benjamin Weinke

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Wells, R. Wells  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

98-101-C

Renews 6-30-98