

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: R-7, North Quarter Corner Section 29, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound & drove charred stake, as per instructions. Re-established by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: No evidence found. By single proportion set a brass disk 2 1/4" in dia. in the top of a conc. cylinder 6"x10", 20" below surface, 1/2" rebar driven to rock imbedded into conc. cylinder. Brass disk stamped as shown in "Monument Marking Detail". New Accessories: TV pole w/Alum. Tag #951, Bearing Object sign, W 98.29 ft. TV pole w/Alum. Tag #951, Bearing Object sign, N 89°39'30" E 200.64 feet. A cedar fence post w/Alum. Tag #951, Bearing Object sign attached. N 22°14'50" W 117.55 feet. A steel fence post w/Bearing Object, Witness Corner signs attached. North 27.16 feet. (Distances to alum. tags)

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/4" brass disk set in concrete 20" below ground.

Existing accessories:

An aluminum tag stamped #951 in West side of a TV pole bears N 89°39'30" E, 200.64 feet.

An aluminum tag stamped #951 in East side of a TV pole bears West, 98.29 feet.

An aluminum tag stamped #951 in South side of a Cedar fence post bears N 22°14'50" W, 117.55 feet.

MONUMENT MARKING DETAIL:

T5N R28E

1 S20

4 S29

1990

LS 951

MONUMENT SET:

New Accessories:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", flush with ground, bears N 34° E, 196.79 feet.

All accessories have bearing object signs attached.

5/8" iron rod has steel fence post with witness post sign attached 1.5 feet beyond rod.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 814049.70

East: 8497807.57

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

RENEW 6-30-98

98-101-C