

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: R-9, Northeast corner Section 29, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 20, 21, 28 & 29; made mound and drove charred stake; as per instructions. Dependent Resurvey by Frank A. Tuers under Special Instructions Group #864, dated April 11, 1975. Record states: Monumented with an iron pipe, 2 ins. diam., firmly set, protruding 4 ins. above ground. Set an iron post, 28 ins. long, 2 1/2 ins. diam., 21 ins. in the ground, with brass cap marked as shown in "Monument Marking Detail". Deposit iron pipe inside the iron post. Maintained by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: Found a 2 1/2" dia. I. pipe with a 3 1/4" Brass Cap marked as shown and as described by Tuers on Page 3 of his field notes. New Accessories: A Cedar fence post S 61° W 33.47 ft. w/Alum. Tag #951. A 5" Locust post N 54° E 1.20 ft. w/Alum. Tag #951 attached. A Cedar fence post N 35° W 30.60 ft. w/Alum. Tag #951 attached. A telephone pole West 58.91 ft. w/Alum. tag #951 attached. Bearing Object signs attached to all accessories. All distances to Alum. Tags.

**MONUMENT AND ACCESSORIES FOUND:**

Found a 3 1/4" brass cap on 2 1/2" iron pipe, 2" above ground surface marked as shown in "Monument Marking Detail".

**Existing Accessories:**

- An aluminum tag stamped #951 in a 6" dead Locust tree bears N 54° E, 1.2 feet.
- An aluminum tag stamped #951 in face of an old fence post bears S 35° W, 30.60 feet.
- An aluminum tag stamped #951 in face of an old fence post bears N 61° W, 33.47 feet.
- An aluminum tag stamped #951 in face of an unmarked power pole bears N 90° W, 58.91 feet.

**MONUMENT MARKING DETAIL:**

U.S. DEPARTMENT OF THE INTERIOR

T5N R28E

S20 | S21

S29 | S28

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGEMENT

**MONUMENT SET:**

**New Accessories:**

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 25° E, 41.61 feet.

A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 30° W, 58.29 feet.

All accessories have bearing object signs attached.

New accessories have steel fence posts with witness post signs attached 1.0 foot beyond.

**LOCATION AND COMMENTS:**

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells  
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 814098.16

East: 8500463.64

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*

*98-101-C*