

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: May 1998

CORNER DESIGNATION: T-5, West Quarter Corner Section 29, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post in mound, with charred stake, as per instructions. Re-established by G. Dennis Edwards, Umatilla County Survey Record #91-01-B, dated January 1991. Record states: Nothing found. Set a 1" x 30" iron pipe with 2 3/8" Brass Cap stamped, as above, 9" above surface and placed a mound of stone to Brass Cap. See Area One 1989 Umatilla County Survey. From which a center pivot Bears N00°49'50"E, 1313.61 feet. A center pivot Bears S00°29'10"E, 1315.49 feet, a pile of stone Bears S27°13'W 10.1 feet, a steel fence post Bears East 2.7 feet. Attached a Bearing Object & Witness Cor. sign to steel post.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/8" brass cap on 1" iron pipe, approximately 3" above ground in a wheat field.

Accessories Found:

A center pivot bears N00°49'50"E, 1313.61 feet.

A center pivot bears S00°29'10"E, 1315.49 feet.

Other accessories destroyed.

MONUMENT MARKING DETAIL:

T5N R28E

1/4

S30 | S29

1990

LS 951

MONUMENT SET:

New Accessories:

A blue "Deep 1" magnet stamped "PLS 1106", 18" in ground bears S52°W, 25.5 feet.

An orange "Deep 1" magnet stamped "PLS 1106", 18" in ground bears N46°W, 30.3 feet.

New Accessories have bearing object signs buried with "Deep 1" magnets.

Corner has steel fence post with witness post sign attached 1.0 feet West.

LOCATION AND COMMENTS: "Deep 1" magnets are magnetic locators manufactured by Bernsten International Company.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 811370.27

East: 8495183.67

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

98-101-C