

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: T-9, East Quarter Corner of Section 29, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and drove charred stake, as per instructions. Re-established by E.T. Eriksen under U.S.R.S. authority of Dept. Instruc. Oct. 24, 1906, dated Feb. 1916. Record states: Establish W (1/4) quarter section corner and mark same with an iron pipe 1 in. in diameter. 24 ins. long, set 22 ins. in ground. Maintained by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Records states: Found a 1" ID x 24" Galv. pipe 6" below the surface of the ground. Pipe was plumb and appeared to be undisturbed. It was set by Eriksen in 1917. In place of the 1" x 24" Iron pipe I set a 1" x 30" iron pipe with a 2 3/8" B.C. stamped as shown in "Monument Marking Detail". Buried the old 1" Iron pipe along side.

**Edwards New Accessories:**

Metal fence post Bears S 32°06' W 461.94 feet.

Metal fence post Bears N 16°15'40" W 477.81 feet.

"X" chiseled in top of 4 foot diameter stone, Bears N 32°06'30" E 303.06 feet.

Metal fence post Bears S 0°05' W 2.20 feet.

Bearing Object signs attached to all accessories, Witness Corner sign attached to steel post S 00°05' W 2.20 feet.

MONUMENT AND ACCESSORIES FOUND: Found a 2 3/8" brass cap on 1" iron pipe, 5" above ground buried next to a 1 1/4" O.D. iron pipe. Brass cap is stamped as shown in "Monument Marking Detail".

**Existing Accessories:**

An "X" chiseled in a 4.0 diameter rock bears N 32°06'30" E, 303.96 feet.

A steel fence post bears N 16°15'40" W, 477.81 feet.

**MONUMENT MARKING DETAIL:**

JLC  
T5N R28E  
1/4 29·28  
1989  
LS 951

**MONUMENT SET:**

**New Accessories:**

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 34° E, 216.10 feet.

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 32°06'30" W, 461.9 feet.

All accessories have bearing object signs attached.

Corner has a steel fence post 2.1 feet South with a witness post sign attached.

LOCATION AND COMMENTS: From Powerline Road East along Canal then South along Canal to end of gravel road, cross Canal at foot bridge, and walk to top of hill.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells  
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:  
North: 811460.66  
East: 8500506.81

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*  
OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6-30-98

98-101-C