

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N RANGE: 29E X-1

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

W1/4 Section 31

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1910 Kimbrell set 2" iron pipe.
In 2003 Edwards drove 5/8"x30" iron rebar into Kimrells iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 5/8" iron rebar 6" below the surface of a graveled road.

MONUMENT DETAIL

T5N
R28E R29E
1/4
36 | 31

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

806380.21
8521815.83

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 57° 25' 00" E 32.76'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 19° 29' 39" W 54.55'
- A 5/8 x 30 Iron Rebar with plastic cap #951 bears S 14° 47' 00" W 70.55'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 19° 06' 27" E 44.59'

LOCATION AND COMMENTS

Corner is on Ott road 0.5 miles North of Punkin Center Road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05