

OREGON CORNER RESTORATION FORM

SECTION 16 TOWNSHIP 5N RANGE 29 E L-9

COUNTY: UMATILLA DATE 7/91
Revised 10/91

CORNER DESIGNATION

West 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed in 1861 by Davenport under Contract #101.
He set post, made mound and drove charred stake.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set 1" x 30" Iron pipe with 2 3/8" Brass Cap, stamped as above, 4" above surface with an 18" diameter ring of stone around. See Co. Survey #91-058-B.

NEW ACCESSORIES From which

- A 1/2" bolt in conc. at edge of bluff Bears. NO° 04' 38"W 1646.82 ft.
- A 5/8" x 30" rebar with Alum. tag #951 Bears. East 12.89 feet,
- An Alum. tag #951 in a 5" diameter wood fence post Bears. SO° 05'W 130.65 ft.
- A steel fence post with witness sign Bears. North 2.7 feet.
- A 1/2" x 24" rebar with Alum. tag #951 Bears. West 9.49 feet.

LOCATION & COMMENTS

From intersection of Craig Rd. with US Hwy. #730, go East on 730 1.0 mile to a fence corner on North R/W. Go North along fence line 4,190 feet to Corner (140 feet North of E-W dirt Rd.)

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 10-91
Rec'd By RK
No. 91-90-R