

OREGON CORNER RESTORATION FORM

SECTION 16 TOWNSHIP 5N RANGE 29E N-11

COUNTY: UMATILLA DATE 7/91
Revised 10/91

CORNER DESIGNATION

South 1/4 Corner

___ CONDITION REPORT ONLY
___ NOT FOUND
___ RENEWED
___ UNRECORDED
X SURVEYED IN
X REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed in 1861 by Davenport under Contract #101.
He set post, made mound and drove charred stake.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found. On 10/17/91 while setting additional references, we found a 2" Iron pipe similar to those set by Kimbrell around 1910 lying S 88°29' W 34.41 feet from my proportioned corner. I held my location because there is no record of said 2" Iron pipe and my location fits other monuments much better than said 2" Iron pipe. See my Survey, Co. #91-058-B.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set 1" x 30" Iron pipe with 2 3/8" Brass Cap, stamped as above, 7" above surface and placed an 18" diameter ring of stone around. See Co. Survey #91-058-B.

NEW ACCESSORIES From which

- A steel fence post with witness sign Bears. North 3.7 ft.
- A 1/2" x 24" rebar with Alum. tag #951 Bears. N89° 15' 07"E 8.30 ft.
- A steel fence post Bears. S0° 08' 44"E 139.2 feet,
- A 1 1/2" washer stamped W.C. 43.75 Bears. N25° 44' 30"W 43.75 feet, glued to 2' high rock face. Also stamped 951.
- A 1 1/2" washer stamped W.C. 19.70 and LS 951 glued to a 1 foot high rock face Bears. S 5°32' W 19.70 feet.
- A found 2" Iron pipe (No record) Bears. S 88°29' W 34.41 feet.

LOCATION & COMMENTS

From intersection of Hwy. #207 & #730, go easterly 0.9 Miles to a fence corner on South R/W line. Corner lies 2,200 feet North.

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor

Date 10-91

Rec'd By KK

No. 91-89-R