

OREGON CORNER RESTORATION FORM

SECTION: 22 TOWNSHIP: 5N

RANGE: 29E

P-17

COUNTY: UMATILLA

DATE: 12/05

CORNER DESIGNATION

E1/4 Section 22

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR29E
 1/4
 22 23
 2005
 L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

817241.40
 8542850.16

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x30" iron pipe in concrete with a 2 3/8" brass cap 2" above the surface stamped as above.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 21° 34' 07" E 71.54'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 83° 27' 43" W 201.56'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 73° 25' 16" W 191.36'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 28° 46' 14" E 108.74'

LOCATION AND COMMENTS

From intersection of Hat Rock Rd with highway 730. Go west 0.2 miles on hwy 730. Corner lies approximately 1200' South of hwy.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05