

OREGON CORNER RESTORATION FORM

SECTION: 27 TOWNSHIP: 5N RANGE: 29E R-15

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

N1/4 Section 27

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITIN AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR2E
1/4 22
27
2005
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

814562.45
8540253.07

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportions I set a 5/8"x30" iron rebar with a 2" aluminum cap stamped as above at the surface of a paved road.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 46°24' 58" E 24.47'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 30° 32' 47" W 19.98'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 62° 28' 30" W 36.01'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 81° 24' 42" W 115.77'

LOCATION AND COMMENTS

From the intersection of Tabor road with Progress road, go East on Progress 0.5 miles to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05