

OREGON CORNER RESTORATION FORM

SECTION: 27 TOWNSHIP: 5N RANGE: 29E T-17

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

E1/4 Section 27

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR29E
 W.C. 1/4 20.00'
 27 | 26
 2005
 L.S 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

811962.87
 8542943.10

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I computed the location.
 Corner falls inside a storage shed. Not set.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 83° 05' 35" E 37.72'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 18° 51' 31" E 118.01'
- A 1"x30" Iron Pipe with 2 3/8" brass cap stamped as above bears N 89° 49' 10" E 20.00'
- A 1"x30" Iron Pipe with 2 3/8" brass cap stamped as above bears N 0° 05' 59" W 20.00'

LOCATION AND COMMENTS

From the intersection of Walls road with Marks road go North on Marks road 0.5 miles to a small storage shed.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH**

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05