

OREGON CORNER RESTORATION FORM

SECTION:33 TOWNSHIP: 5N RANGE: 29E V-11

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

N1/4 Section 33

- CONDITION REPORT ONLY*
- NOT FOUND*
- RENEWED*
- UNRECORDED*
- SURVEYED IN*
- REFERENCED OUT*

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1913 Kimbrell set a 3" iron pipe.
In 1990 Edwards set a 2 1/2" brass disk in concrete over 3" iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 2 1/2" brass disk at surface of a paved road stamped as below.
W.C. a 5/8" iron rebar with plastic cap #951 bears N 44° 45' 43" W 30.43'(30.35')
W.C. a 5/8" iron rebar with plastic cap #951 bears S 44° 56' 50" E 26.72'(26.78')
W.C. an aluminum tag #951 in a R/R tie bears S 58° 03' 14" W 50.54'(50.50')

MONUMENT DETAIL

T5NR29E
1/4 28
33
1990
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809191.76
8535059.07

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 76° 31' 53" E 76.05'

LOCATION AND COMMENTS

At the intersection of Golda road & Walls road. (On Walls Road 1/2 mile East of Edwards road)

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05