

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N RANGE: 29E V-5

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NE Section 31

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1910 Kimbrell set a 3/4" iron pipe.
In 1984 Edwards set a 2" brass disk in concrete over iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found a 2" brass disk at the surface of a paved road stamped as below.
W.C. an aluminum tag # 951 in a power pole bears S 73° 57' 14" E 71.18'(71.20')
W.C. an aluminum tag # 951 in a power pole bears N 51° 11' 05" W 40.09'(40.03')
W.C. an aluminum tag #951 in a R/R tie fence post bears S 49° 58' 41" E 33.58'(33.06')

MONUMENT DETAIL

T5NR29E
30 | 29
31 | 32
1989
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809100.87
8527100.43

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 55° 51' 19" W 26.44'

LOCATION AND COMMENTS

At the intersection of Craig road & Walls road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05