

OREGON CORNER RESTORATION FORM

SECTION 33, 34 TOWNSHIP 5 NORTH RANGE 29 EAST
COUNTY : UMATILLA DATE DEC/22

X-13

CORNER DESIGNATION

1/4 CORNER

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNCOVERED
- SURVEYED IN
- REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101, HE SET POST AND MADE MOUND.
IN 1913 KIMBRELL SET A 2" IRON PIPE.
IN 2002 LS 951 SET A 5/8" IRON ROD INSIDE 2" IRON PIPE.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 5/8" IRON ROD.
FOUND ALUMINUM TAG IN POWER POLE STAMPED LS 951 BEARS S 56°06'32" W, 41.38'.
FOUND ALUMINUM TAG IN POWER POLE STAMPED LS 951 BEARS S 32°02'09" E, 28.16'.
FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS S 45°42'03" W, 31.43'.
FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS S 33°31'03" E, 24.36'.

MONUMENT DETAIL



NAD 83/91
OREGON STATE PLANE
INTERNATIONAL FEET

806603.40
8537755.71

MONUMENT SET (PROCEDURES AND DESCRIPTION)

SET 2" ALUMINUM CAP STAMPED AS ABOVE OVER FOUND 5/8" IRON ROD.

NEW ACCESSORIES FROM WHICH

LOCATION AND COMMENTS

CORNER FALLS AT THE INTERSECTION
OF TABOR ROAD AND COLUMBIA
LANE.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.
P.O. BOX 1322
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Brit L. Primm
OREGON
JULY 13, 1999
BRIT L. PRIMM
48509

EXPIRATION DATE: 12/31/24