

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N RANGE: 29E Z-1

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SW Section 31

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Maxon & Hurd under Contract # 50 in 1860. They set post and made mound.
 In 1910 Kimbrell found corner in Co. Survey #306
 In 1978 LaGier set 5/8" iron rebar.
 In 1980 Krumbein set 2 1/2" brass cap.
 In 1984 Cramer set R/R spike in survey for Vernon.
 In 1997 Roberts computed location in survey for Holguin.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 5/8" iron rebar N 66° 27' 02" E 12.64'
 Found 2 1/2" brass cap N 41° 34' 29" E 13.95'

MONUMENT DETAIL

T5N
 R28E | R29E
 S36 | S 31
 T4NR29E S6
 2005
 L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

803764.83
 8521857.14

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By intersecting Kimbell's 1910 survey of the West line of section 31 with monuments on the standard parallel line, I set a 5/8"x30" iron rebar with a 2" aluminum cap stamped as above flush with the pavement. This matches Cramer and Roberts surveys.

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 66° 38' 01" W 87.58'
 A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 24° 11' 45" W 17.69'
 A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 69° 31' 02" E 99.53'

LOCATION AND COMMENTS

At the intersection of Ott road (north) and Punkin Center road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05